



REPLY TO PRE BID QUERIES

FOR

LAYING OF PE 100 PIPE AT COTONOU, BENIN OF WEST AFRICA.

Tender No.: AIP/REPL/004/C-PE

Client : SIPI -Benin

Consultant : REPL

Date / Time of Pre- Bid Meeting: 16/08/2023 @ 10:30 Hrs (WAT)

Date of Pre-bid Clarifications: 22.08.2023



Sr. No.	Tender Clause No. / Annexures	Bidder's Query/Clarification	SIPI-Benin/REPL Reply
TECHNICAL			
1	Technical Volume II of II	Kindly clarify to us what is the unit of measurement "RM" mean in item 6.1 and 6.2 of the SOR, Should we take running meter to mean Square Meters since Asphalt is measured in Square meter.	Unit written as "RM" means "Running Meter", running meter unit is to restrict the width of trench as per standard drawing attached in technical volume.
2	Technical Volume II of II	In case the selected contractor opts not to use HDD, will the client object	You cannot avoid HDD at certain places as we may not have other options there , however we will try to keep the HDD part as minimum and try to avoid it unless site condition demand.